

# Premium Dessert Maker Rhokett Selects ISD Solutions for New 'Clean Room' Production Facility

panels with a food safe laminate skin to form the walls and ceilings, with bespoke trims and detailing around columns, alcoves, doors, stairs and lifts as well as ovens, chillers and freezers. Services as well as plumbing for eight sink stations are cleverly concealed within the panel core.

Approximately 95% of fittings and finishes were designed and manufactured by ISD Solutions' in house team ensuring greater accuracy, flexibility to meet client requirements and high quality for the 12 week project.

Rhokett Chairman Peter Le Voir said: "The new clean room style facility in Cranbrook delivers the capacity we need to meet high levels of demand for our bespoke desserts. ISD Solutions' expertise in composite panel coldstores, technical knowledge, flexibility and high quality workmanship, has helped to deliver a first class solution to support Rhokett's continued expansion."

<http://www.isd-solutions.co.uk/>



enquiry 507  
[www.mclink.co.uk/1006-507](http://www.mclink.co.uk/1006-507)



Specialist composite panel contractor ISD Solutions has completed the fit out of new high care production facilities for Rhokett, the rapidly expanding luxury high volume dessert maker, which supplies big name customers including Marks and Spencer, Waitrose, Pret A Manger and Sainsbury's.

The new 1410m<sup>2</sup> food processing centre at Cranbrook in Kent, will provide Rhokett with further capacity to match high levels of demand for its upmarket cheesecake and patisserie range. Rhokett was established in 2002 with the support of Michelin-star chef Gary Rhodes and is currently seeing growth of more than 20% a year.

Under the £150,000 contract ISD Solutions' Coldstore division was responsible for the design and ground

floor fit out of the new warehouse, incorporating manufacturing and food preparation rooms, as well as cleaning, wash-down and lobby areas.

To meet extremely high food safety standards the team worked side by side with Rhokett to deliver a temperature controlled clean room type installation with minimal ledges, flush walls and where possible fixing free.

The construction includes a total of 2,200m<sup>2</sup> 100mm PIR (Polyisocyanurate)